



Anderson Enterprises, Inc
Anderson Enterprises, Inc
4420 South 228th Plaza
Elkhorn, NE 68022

Phone: (402) 894-0999

Company Representative
Chris Baumgart
Phone: (402) 212-7337
cjbaumgart@hotmail.com

04/16/2026
Claim Information

Madisyn Van Den Boogart McNeil. Company

1672 South 150th Avenue
Omaha, NE 68144
(402) 881-7745

Job: Madisyn Van Den Boogart McNeil. Company

Roofing Section

- Ostronic Residence New Construction

- Install 6' of ice and water shield at all gutter lines, rakes edges, and valleys.
- Install Synthetic underlayment to keep the roof dry.
- Install Starter Shingles along all gutter perimeter and rake edges.
- Install CertainTeed Presidential Shingles Impact Resistant per manufacturers specifications using 1 3/4" electro-galvanized roofing nails.
- Install Hip & Ridge Shingles.
- Install new Ohagin vents
- Install new pipe
- Wall flashing, headwall flashing and step flashing
- Clean up all job-related debris.
- Provide owner with an CertainTeed Manufacturer Warranty on products.
- Our Crews are licensed and insured.
- Crews will maintain safety requirement at all times during the construction process.

Shingles

CertainTeed Presidential Shake IR (5 BD/SQ)

CertainTeed Presidential Starter IR (36')

CertainTeed SwiftStart - 7 5/8" (116')

CertainTeed CedarCrest Hip & Ridge Cap (20')

Underlayment

ABC Pro Guard 20 Synthetic Underlayment (10 sq)

IKO StormTamer Ice & Water Shield (2 sq)

Flashings

Galvanized Steel Roof to Wall Flashing - 7/12 Pitch - 4"x4" (10')

Phillips EdgeMaster Tile Pan Flashing - 4"x4"x10'

IPS Galvanized Steel Base Pipe Flashing - 1 1/4"-4"

Galvanized Steel Drip Edge - D Style - 5" (10')

Galvanized Steel W Valley Metal - 24" (10')

Phillips EdgeMaster Tile Pan Flashing - 4"x4"x10'

Vents

O'Hagin Galvanized Composition Shingle Vent - 4" Flange - 1/4" Galvanized Wire Mesh - Black

Fasteners

Electro Galvanized Steel Roofing Coil Nails - 1 3/4" (7200 Cnt)

ABC Electro Galvanized Plastic Cap Nails - Ring Shank - 1" (2000 Cnt)

Caulking

Geocel 2320 Gutter & Narrow Seam Sealant (10.3 oz)

Labor

Steep Slope - Install Laminated Shingles

Steep Fee - 7/12 to 9/12	
Steep Fee - 12/12 Pitch	
Standing Seam Package	
Resisto Lastobond Smooth Seal HT Ice & Water Shield (1.94 sq)	
	\$45,825.22

Gutters Section	
6" Gutters	
Install 6" seamless aluminum gutters and 3"x4" downspouts	
Install 6" gutters and downspouts	
	\$3,199.64

TOTAL	\$49,024.86
-------	-------------

-All material is guaranteed to be as specified, and the above work to be performed in accordance with manufactures specifications.
-Replacement of deteriorated decking, fascia boards, roof jacks, ventilators, flashing or other materials, as well as structural repairs, unless otherwise stated in this proposal are not included. Any additional materials or labor will result in an additional charge
-All agreements are contingent on delays beyond our control
-Should materials have to be restocked or reorder due to cancellations by the customer, there will be a restocking fee equal to 15% of the proposal price.
-All material warranties stated or implied herein are maintained by the material manufacture, not Anderson Roofing
-Any available warranties will be logged
-Labor warranties does not cover damage caused by lightening, gale force winds, hailstorms, or other violent storm or foreign object damage
-Payment to be made upon completion of work.
-All discounts and warranties are void if balance is not paid in full.
-Anderson Roofing is not responsible for any exisiting fungus, mold, mildew, spores or rot
-The above prices, specifications and conditions are satisfactory and hereby accepted. You are authorized to do the work as specified. Payments will be made as outlines above
-All past due sums under this proposal will bear interest at the rate of 1.5% per month until paid in full.

Company Authorized Signature

Date

Customer Signature

Date