Contract - Detailed

Pella Window and Door Showroom of Omaha
14478 Crest Rd.
Omaha, NE 68138
Phone: (402) 331-9225 **Fax:** (402) 331-3076

Sales Rep Name: Drobny, Brian
Sales Rep Phone: (402) 660-7148
Sales Rep Fax:
Sales Rep E-Mail: briandrobny@pellaomaha.com

Customer Information

McNeil Company Builders
4666 S 132nd Street

OMAHA, NE 68137
Primary Phone:
Mobile Phone:
Fax Number: (402) 3330182
E-Mail: accounting@mcneilcompany.com
Contact Name:

Great Plains #: MCNEILBLDR
Customer Number: 1002066689
Customer Account: 1000228280

Project/Delivery Address

811 N 143rd Plaza/Hogan/McNeil Co
811 N 143rd Plaza

Lot #
OMAHA, NE 68154
County: DOUGLAS
Owner Name:

Owner Phone:

Order Information

Quote Name: Iron Ore LS2 6/29/26

Order Number: 230
Quote Number: **21006962**
Order Type: Installed Sales
Wall Depth:
Payment Terms: Net 30 Days
Tax Code: USETAX
Cust Delivery Date: None
Quoted Date: 6/26/2026
Contracted Date:
Booked Date:
Customer PO #:

Accessories Managed / Delivery Date

Door Handles	8/21/2026	Hinge & Sliding Door Screens	8/21/2026	Window Screens	8/21/2026	Window Hardware	8/21/2026

Customer Notes: LIFESTYLE DUAL PANE SERIES
Iron Ore Exterior
Unfinished Interior
Champagne Hardware
Champagne Screen Frames
Advanced Low-E Glass
SDL Grilles w/Spacer

Full Pella STEADY SET Install, Zip Wall

Line #	Location:	Attributes
10	LL Bed 3	



Viewed From Exterior

PK #
2242

Lifestyle, 2-Wide Casement, 58 X 53, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$1,356.95	1	$1,356.95

1: 2953 Left Casement
Frame Size: 29 X 53
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
2: 2953 Right Casement
Frame Size: 29 X 53
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Foldout Fins, Factory Applied, No Head Drip Cap, No Exterior Trim, 3-11/16", 5", Factory Applied, Manufacturer Recommended Clearance, Perimeter Length = 222".

Rough Opening: 58 - 3/4" X 53 - 3/4"

Customer Notes: **NO JAMB EXTENSION. FOUNDATION WALL **

* FLOOR PLANS & ELEVATIONS ARE DIFFERENT. QUOTED PER ELEVATION *

21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	19
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	19

Line #	Location:	Attributes
15	LL Bed 2	



Viewed From Exterior

PK #
2242

Lifestyle, 2-Wide Casement, 58 X 53, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$1,356.95	1	$1,356.95

1: 2953 Left Casement
Frame Size: 29 X 53
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
2: 2953 Right Casement
Frame Size: 29 X 53
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Foldout Fins, Factory Applied, No Head Drip Cap, No Exterior Trim, 3-11/16", 5", Factory Applied, Manufacturer Recommended Clearance, Perimeter Length = 222".

Rough Opening: 58 - 3/4" X 53 - 3/4"

Customer Notes: ** NO JAMB EXTENSION. FOUNDATION WALL **

21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	19
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	19

Line #	Location:	Attributes
20	LL Fitness	

Lifestyle, 2-Wide Sash Set, 82 X 47, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$1,401.33	1	$1,401.33



Viewed From Exterior

PK #
2242

1: 4147 Fixed Sash Set
Frame Size: 41 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
2: 4147 Fixed Sash Set
Frame Size: 41 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Foldout Fins, Factory Applied, No Head Drip Cap, No Exterior Trim, 3-11/16", 5", Factory Applied, Manufacturer Recommended Clearance, Perimeter Length = 258".

Rough Opening: 82 - 3/4" X 47 - 3/4"

Customer Notes: **NO JAMB EXTENSION. FOUNDATION WALL **

21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	22
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	22

Line #	Location:	Attributes
25	LL Family Room	

Lifestyle, 3-Wide Sash Set, 141 X 47, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$2,243.56	1	$2,243.56



Viewed From Exterior

PK #
2242

1: 4747 Fixed Sash Set
Frame Size: 47 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
2: 4747 Fixed Sash Set
Frame Size: 47 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
3: 4747 Fixed Sash Set
Frame Size: 47 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Vertical Mull 2: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Foldout Fins, Factory Applied, No Head Drip Cap, No Exterior Trim, 3-11/16", 5", Factory Applied, Manufacturer Recommended Clearance, Perimeter Length = 376".

Rough Opening: 142" X 48"

Customer Notes: **NO JAMB EXTENSION. FOUNDATION WALL **

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	32
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	32

Line #	Location:	Attributes
30	Office	



Viewed From Exterior

PK #
2242

Lifestyle, 2-Wide Casement, Lifestyle, 2-Wide Sash Set, 64 X 92, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$3,452.60	1	$3,452.60

1: 3271 Left Casement
Frame Size: 32 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Tempered Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.25, VLT 0.46, CPD PEL-N-14-00687-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: SDL w/Spacer, No Custom Grille, 7/8", Traditional (1W3H)
2: 3271 Right Casement
Frame Size: 32 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Tempered Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.25, VLT 0.46, CPD PEL-N-14-00687-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: SDL w/Spacer, No Custom Grille, 7/8", Traditional (1W3H)
3: 3221 Fixed Sash Set
Frame Size: 32 X 21
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00861-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20653
Grille: No Grille,
4: 3221 Fixed Sash Set
Frame Size: 32 X 21
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00861-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20653
Grille: No Grille,
Horizontal Mull 1: FactoryMull, Reinforcing Plate, Frame To Frame Width- 0", Mull Design Pressure- 20, Overall Thru Direction- Horizontal
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Horizontal
Vertical Mull 2: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Horizontal
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Head Drip Cap, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 312".

Rough Opening: 64 - 3/4" X 92 - 3/4"

21DRINST0050 - A - Window Install Per LF - NCI - Whole House Qty 27

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI Qty 27

Line #	Location:	Attributes
35	Front Entry	

Front Entry System - Provided by Others

Item Price	Qty	Ext'd Price
$0.00	1	$0.00

Line #	Location:	Attributes
40	Stair Landing	

Lifestyle, Sash Set, Lifestyle, Sash Set, 32 X 92, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$1,642.88	1	$1,642.88

Viewed From Exterior

PK #
2242

1: 3271 Fixed Sash Set
Frame Size: 32 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Tempered Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.28, SHGC 0.28, VLT 0.51, CPD PEL-N-229-00951-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: SDL w/Spacer, No Custom Grille, 7/8", Traditional (1W3H)
2: 3221 Fixed Sash Set
Frame Size: 32 X 21
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00861-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20653
Grille: No Grille,
Horizontal Mull 1: FactoryMull, Standard Joining Mullion, Frame To Frame Width- 0", Mull Design Pressure- 20
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 248".

Rough Opening: 32 - 3/4" X 92 - 3/4"

21DRINST0050 - A - Window Install Per LF - NCI - Whole House Qty 21

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI Qty 21

Line #	Location:	Attributes
45	Powder Bath T.C.	



Viewed From Exterior

PK #
2242

Lifestyle, Casement Right, 25 X 53, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$795.78	1	$795.78

1: 2553 Right Casement
Frame Size: 25 X 53
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.25, VLT 0.47, CPD PEL-N-14-00679-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Clear Opening Width 15.25, Clear Opening Height 48.875, Clear Opening Area 5.175998, Egress Does not meet typical United States egress, but may comply with local code requirements
Grille: SDL w/Spacer, No Custom Grille, 7/8", Traditional (1W2H)
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 156".

Rough Opening: 25 - 3/4" X 53 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	14
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	14

Line #	Location:	Attributes

50 3 Car Garage



Viewed From Exterior

PK #
2242

Lifestyle, 2-Wide Sash Set, 70 X 71, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$2,072.68	1	$2,072.68

1: 3571 Fixed Sash Set
Frame Size: 35 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.28, SHGC 0.28, VLT 0.51, CPD PEL-N-229-00951-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: SDL w/Spacer, No Custom Grille, 7/8", Traditional (1W3H)
2: 3571 Fixed Sash Set
Frame Size: 35 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.28, SHGC 0.28, VLT 0.51, CPD PEL-N-229-00951-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: SDL w/Spacer, No Custom Grille, 7/8", Traditional (1W3H)
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Head Drip Cap, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 282".

Rough Opening: 70 - 3/4" X 71 - 3/4"

21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	24
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	24

Line #	Location:	Attributes

55 3 Car Garage



Viewed From Exterior

PK #
2242

Lifestyle, Sash Set, Fixed, 32 X 59, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$769.80	1	$769.80

1: 3259 Fixed Sash Set
Frame Size: 32 X 59
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00861-00001, Performance Class LC, PG 45, Calculated Positive DP Rating 45, Calculated Negative DP Rating 45, FPA FL20653
Grille: No Grille,
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 182".

Rough Opening: 32 - 3/4" X 59 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI Qty 16

21DRINST0050 - A - Window Install Per LF - NCI - Whole House Qty 16

Line #	Location:	Attributes

60 Primary Wardrobe

Viewed From Exterior

PK #
2242

Lifestyle, Casement Left, 25 X 47, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$662.06	1	$662.06

1: 2547 Left Casement
Frame Size: 25 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Clear Opening Width 15.25, Clear Opening Height 42.875, Clear Opening Area 4.540582, Egress Does not meet typical United States egress, but may comply with local code requirements
Grille: No Grille,
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 144".

Rough Opening: 25 - 3/4" X 47 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI Qty 13

21DRINST0050 - A - Window Install Per LF - NCI - Whole House Qty 13

Line #	Location:	Attributes
65	Primary Bath T.C.	

Viewed From Exterior

PK # 2242

Lifestyle, Casement Left, 25 X 47, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$662.06	1	$662.06

1: 2547 Left Casement
Frame Size: 25 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Clear Opening Width 15.25, Clear Opening Height 42.875, Clear Opening Area 4.540582, Egress Does not meet typical United States egress, but may comply with local code requirements
Grille: No Grille,
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 144".

Rough Opening: 25 - 3/4" X 47 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	13
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	13

Line #	Location:	Attributes
70	Primary Bath Sink	



Viewed From Exterior

PK # 2242

Lifestyle, Sash Set, Fixed, 29 X 17, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$350.81	3	$1,052.43

1: 2917 Fixed Sash Set
Frame Size: 29 X 17
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00861-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20653
Grille: No Grille,
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 92".

Rough Opening: 29 - 3/4" X 17 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	8
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	8

Line #	Location:	Attributes
75	Primary Bath Sink	



Viewed From Exterior

PK #
2242

Lifestyle, Casement Right, 25 X 47, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$662.06	1	$662.06

1: 2547 Right Casement
Frame Size: 25 X 47
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 50, Calculated Positive DP Rating 50, Calculated Negative DP Rating 50, FPA FL20675, STC 25, OITC 22, Clear Opening Width 15.25, Clear Opening Height 42.875, Clear Opening Area 4.540582, Egress Does not meet typical United States egress, but may comply with local code requirements
Grille: No Grille,
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 144".

Rough Opening: 25 - 3/4" X 47 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	13
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	13

Line #	Location:	Attributes
80	Primary Bed	



Viewed From Exterior

PK #
2242

Lifestyle, Casement, Sash Set, Casement, 99 X 71, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$2,949.51	1	$2,949.51

1: 2971 Left Casement
Frame Size: 29 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.28, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00685-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
2: 4171 Fixed Sash Set
Frame Size: 41 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
3: 2971 Right Casement
Frame Size: 29 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.28, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00685-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Vertical Mull 2: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Head Drip Cap, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 340".

Rough Opening: 99 - 3/4" X 71 - 3/4"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	29
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	29

Line #	Location:	Attributes
85	Lounge Door	



Viewed From Exterior

PK #
2242

Lifestyle, Double Sliding Door, Contemporary,, Vent Right / Fixed, 95.25 X 95.5, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$3,853.27	1	$3,853.27

1: 9696 Vent Right / Fixed Double Sliding Door
Frame Size: 95 1/4 X 95 1/2
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Factory Assembled, Standard, Clad, Pine, 5 7/8", 4 9/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Sash / Panel: Square, Square
Glass: Insulated Tempered Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Frame Selection: Wood Trim Cover, Factory Applied
Hardware Options: Vent Lock, Black, No Keylock Included, No Handle, No Handle, No Integrated Sensor
Screen: Sliding Screen, Iron Ore, Black, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.30, SHGC 0.28, VLT 0.51, CPD PEL-N-304-00155-00001, Performance Class LC, PG 35, Calculated Positive DP Rating 35, Calculated Negative DP Rating 35, FPA FL47325, STC 28, OITC 24
Grille: No Grille,
Wrapping Information: Foldout Fins, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Factory Supplied, Shipped Separately, Manufacturer Recommended Clearance, Perimeter Length = 382".

Rough Opening: 96" X 96"

21DRINST0200 - C - 2 Panel Door per LF - NCI - Whole House	Qty	32
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	32

Line #	Location:	Attributes
90	Plazo Handle Set	

Viewed From Exterior

PK #
2242

05930001 - Pella Plazo Sliding Patio Door Handle Set XO, Satin Nickel

Item Price	Qty	Ext'd Price
$376.51	1	$376.51

1: Pella Parts Catalog
Pella Parts Selector: Door Hardware, Sliding Patio Door, Interior / Exterior Handle Sets, Architect Series, Satin Nickel, Satin Nickel, Vent Right / Fixed, 05930001, Plazo Sliding Patio Door Handle Set XO, Satin Nickel, 05930001, Greater than 96-in,

Rough Opening: 10" X 10.5"

Line #	Location:	Attributes
95	Dining Door	



Viewed From Exterior

PK #
2242

Lifestyle, Double Sliding Door, Contemporary,, Fixed / Vent Left, 95.25 X 95.5, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$3,853.27	1	$3,853.27

1: 9696 Fixed / Vent Left Double Sliding Door
Frame Size: 95 1/4 X 95 1/2
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Factory Assembled, Standard, Clad, Pine, 5 7/8", 4 9/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Sash / Panel: Square, Square
Glass: Insulated Tempered Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Frame Selection: Wood Trim Cover, Factory Applied
Hardware Options: Vent Lock, Black, No Keylock Included, No Handle, No Handle, No Integrated Sensor
Screen: Sliding Screen, Iron Ore, Black, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.30, SHGC 0.28, VLT 0.51, CPD PEL-N-304-00155-00001, Performance Class LC, PG 35, Calculated Positive DP Rating 35, Calculated Negative DP Rating 35, FPA FL47325, STC 28, OITC 24
Grille: No Grille,
Wrapping Information: Foldout Fins, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Factory Supplied, Shipped Separately, Manufacturer Recommended Clearance, Perimeter Length = 382".

Rough Opening: 96" X 96"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	32
21DRINST0200 - C - 2 Panel Door per LF - NCI - Whole House	Qty	32

Line #	Location:	Attributes
100	Plazo Handle Set	

Viewed From Exterior

PK #
2242

05930005 - Pella Plazo Sliding Patio Door Handle Set OX, Satin Nickel

Item Price	Qty	Ext'd Price
$348.31	1	$348.31

1: Pella Parts Catalog
Pella Parts Selector: Door Hardware, Sliding Patio Door, Interior / Exterior Handle Sets, Architect Series, Satin Nickel, Satin Nickel, Fixed / Vent Left, 05930005, Plazo Sliding Patio Door Handle Set OX, Satin Nickel, 05930005, Greater than 96-in,

Rough Opening: 10" X 10.5"

Line #	Location:	Attributes
105	Dining	

Lifestyle, 3-Wide Casement, 105 X 71, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$2,908.53	1	$2,908.53



PK #
2242

Viewed From Exterior

1: 3571 Left Casement
Frame Size: 35 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.28, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00685-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
2: 3571 Fixed Sash Set
Frame Size: 35 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.27, SHGC 0.31, VLT 0.58, CPD PEL-N-229-00949-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
3: 3571 Right Casement
Frame Size: 35 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.28, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00685-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20675, STC 25, OITC 22, Egress Meets minimum clear opening and 5.7 sq.ft
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Vertical Mull 2: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Head Drip Cap, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 352".

Rough Opening: 105 - 3/4" X 71 - 3/4

21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	30
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	30

Line #	Location:	Attributes
110	Gathering Room	

Lifestyle, 3-Wide Sash Set, 141 X 71, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$3,288.83	1	$3,288.83



Viewed From Exterior

PK #
2242

1: 4771 Fixed Sash Set
Frame Size: 47 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.28, SHGC 0.30, VLT 0.57, CPD PEL-N-229-00965-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
2: 4771 Fixed Sash Set
Frame Size: 47 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.28, SHGC 0.30, VLT 0.57, CPD PEL-N-229-00965-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
3: 4771 Fixed Sash Set
Frame Size: 47 X 71
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Performance Information: U-Factor 0.28, SHGC 0.30, VLT 0.57, CPD PEL-N-229-00965-00001, Performance Class LC, PG 30, Calculated Positive DP Rating 30, Calculated Negative DP Rating 30, FPA FL20653, STC 28, OITC 24
Grille: No Grille,
Vertical Mull 1: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Vertical Mull 2: FactoryMull, Standard Joining Mullion, Mull Design Pressure- 20, Overall Thru Direction- Vertical
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Head Drip Cap, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 424".

Rough Opening: 142" X 72"

21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	36
21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	36

Line #	Location:	Attributes
115	Office	

Viewed From Exterior

Lifestyle, Casement Left, 25 X 59, Without HGP, Iron Ore

Item Price	Qty	Ext'd Price
$774.14	2	$1,548.28

PK # 2242

1: 2559 Left Casement
Frame Size: 25 X 59
Unit Type: No Program
General Information: No Package, Without Hinged Glass Panel, Clad, Pine, 5", 3 11/16"
Exterior Color / Finish: Standard Enduraclad, Iron Ore
Interior Color / Finish: Unfinished Interior
Glass: Insulated Low-E Advanced Low-E Insulating Glass Argon Non High Altitude
Hardware Options: Wash Hinge Hardware, Fold-Away Crank, Champagne, No Window Opening Control Device, No Limited Opening Hardware, No Integrated Sensor, Shipped Separate, Accessory Managed
Screen: Full Screen, Champagne, InView™ , Shipped Separate, Accessory Managed
Performance Information: U-Factor 0.29, SHGC 0.27, VLT 0.51, CPD PEL-N-14-00677-00001, Performance Class LC, PG 45, Calculated Positive DP Rating 45, Calculated Negative DP Rating 45, FPA FL20675, STC 25, OITC 22, Clear Opening Width 15.25, Clear Opening Height 54.875, Clear Opening Area 5.811415, Egress Does not meet typical United States egress, but may comply with local code requirements
Grille: No Grille,
Wrapping Information: Steady Set - Interior Install, Factory Applied, No Exterior Trim, 6-9/16", 7 7/8", Standard Four Sided Jamb Extension, Factory Applied, 2x6 Bracket, Manufacturer Recommended Clearance, Perimeter Length = 168".

Rough Opening: 25 - 3/4" X 59 - 3/4"

Customer Notes: * FLOOR PLANS & ELEVATIONS ARE DIFFERENT. QUOTED PER ELEVATION *

21DRINST0050 - A - Window Install Per LF - NCI - Whole House	Qty	15
21DRINST1000 - F - ADDER - Zip Tape Install Per LF - NCI	Qty	15

Line #	Location:	Attributes
120	Head Drip Flashing	

Head Drip Flashing, Length: 192, Iron Ore

Item Price	Qty	Ext'd Price
$83.90	10	$839.00

PK # 2242

1: Accessory
Frame Size: -1 X -1
General Information: Head Drip Flashing
Exterior Color / Finish: Painted, Standard Enduraclad, Iron Ore
Wrapping Information: Perimeter Length = 0".

Viewed From Exterior

Line #	Location:	Attributes	Item Price	Qty	Ext'd Price
125	Install Package	**21NCI0300 - Install Package**	$2,173.00	1	$2,173.00

Thank You For Purchasing Pella® Products

PELLA WARRANTY:

Pella products are covered by Pella's limited warranties in effect at the time of sale. All applicable product warranties are incorporated into and become a part of this contract. Please see the warranties for complete details, taking special note of the two important notice sections regarding installation of Pella products and proper management of moisture within the wall system. Neither Pella Corporation nor the Seller will be bound by any other warranty unless specifically set out in this contract. However, Pella Corporation will not be liable for branch warranties which create obligations in addition to or obligations which are inconsistent with Pella written warranties.

Clear opening (egress) information does not take into consideration the addition of a Rolscreen [or any other accessory] to the product. You should consult your local building code to ensure your Pella products meet local egress requirements.

Per the manufacturer's limited warranty, unfinished mahogany exterior windows and doors must be finished upon receipt prior to installing and refinished annually, thereafter. Variations in wood grain, color, texture or natural characteristics are not covered under the limited warranty.

INSYNCTIVE PRODUCTS: In addition, Pella Insynctive Products are covered by the Pella Insynctive Products Software License Agreement and Pella Insynctive Products Privacy Policy in effect at the time of sale, which can be found at Insynctive.pella.com. By installing or using Your Insynctive Products you are acknowledging the Insynctive Software Agreement and Privacy Policy are part of the terms of sale.

Notice of Collection of Personal Information: We may collect your personal information when you interact with us. Under the California Consumer Privacy Act (CCPA), California residents have specific rights to request this information, request to delete this information, and opt out of the sharing or sale of this information to third parties. To learn more about our collection practices and your rights under the CCPA please visit our link https://www.pella.com/california-rights-policy/ at pella.com.

ARBITRATION AND CLASS ACTION WAIVER ("ARBITRATION AGREEMENT")

YOU and Pella and its subsidiaries and the Pella Branded Distributor **AGREE TO ARBITRATE DISPUTES ARISING OUT OF OR RELATING TO YOUR PELLA PRODUCTS (INCLUDES PELLA GOODS AND PELLA SERVICES) AND WAIVE THE RIGHT TO HAVE A COURT OR JURY DECIDE DISPUTES. YOU WAIVE ALL RIGHTS TO PROCEED AS A MEMBER OR REPRESENTATIVE OF A CLASS ACTION, INCLUDING CLASS ARBITRATION, REGARDING DISPUTES ARISING OUT OF OR RELATING TO YOUR PELLA PRODUCTS.** You may opt out of this Arbitration Agreement by providing notice to Pella no later than ninety (90) calendar days from the date You purchased or otherwise took ownership of Your Pella Goods. To opt out, You must send notice by e-mail to pellawebsupport@pella.com , with the subject line: “Arbitration Opt Out” or by calling (877) 473-5527. Opting out of the Arbitration Agreement will not affect the coverage provided by any applicable limited warranty pertaining to Your Pella Products. For complete information, including the full terms and conditions of this Arbitration Agreement, which are incorporated herein by reference, please visit www.pella.com/arbitration or e-mail to pellawebsupport@pella.com, with the subject line: “Arbitration Details” or call (877) 473-5527. D'ARBITRAGE ET RENONCIATION AU RECOURS COLLECTIF ("convention d'arbitrage") EN FRANÇAIS SEE PELLA.COM/ARBITRATION. DE ARBITRAJE Y RENUNCIA COLECTIVA ("acuerdo de arbitraje") EN ESPAÑOL VER PELLA.COM/ARBITRATION.

Seller shall not be held liable for failure or delay in the performance of its obligations under this Agreement, if such performance is hindered or delayed by the occurrence of an act or event beyond the Seller’s reasonable control (force majeure event), including but not limited to earthquakes, unusually severe weather and other Acts of God, fire, strikes and labor unrest, epidemics, riots, war, civil unrest, and government interventions. Seller shall give timely notice of a force majeure event and take such reasonable action to mitigate the impacts of such an event.

Product Performance Information:

U-Factor, Solar Heat Gain Coefficient (SHGC), and Visible Light Transmittance (VLT) are certified by the National Fenestration Rating Council (NFRC).

Manufacturer stipulates that these ratings conform to applicable NFRC procedures for determining whole product performance. NFRC ratings are determined for a fixed set of environmental conditions and a specific product size. NFRC does not recommend any products and does not warrant the suitability of any product for any specific use.

Design Pressure (DP), Performance Class, and Performance Grade (PG) are certified by a third party organization, in many cases the Window and Door Manufacturers Association (WDMA). The certification requires the performance of at least one product of the product line to be tested in accordance with the applicable performance standards and verified by an independent party. The certification indicates that the product(s) of the product line passed the applicable tests. The certification does not apply to mulled and/or product combinations unless noted. Actual product results will vary and change over the products life.

For more performance information along with information on Florida Product Approval System (FPAS) Number and Texas Dept. of Insurance (TDI) number go to www.pella.com/performance.

Including during the construction period, casement windows should never be left open and unlocked for prolong periods or during high wind conditions to avoid sash detachment/damage.

Actual sizes tested for documented STC and OITC ratings may vary from the ASTM E 1425 sizes to better represent Pella product offering.

STC and OITC ratings shown may be conservatively based on products tested with thinner panes of glass.

STC and OITC ratings may be from test results from an equivalent product.

New Construction :

PAYMENT TERMS:

WARRANTY: Pella® products are covered by Pella's limited warranties in effect at the time of sale. All applicable product warranties are incorporated into and become a part of this contract. Please see the warranties for complete details. Neither Pella Corporation nor Pella Products of Omaha and Lincoln will be bound by any other warranty. Please be aware that product which is not fully paid for is not covered by the warranty.

RETURN FEES: A 50% Fee will be charged for all items cancelled by the customer after the Last Revision Date. Your sales representative can provide you with information related to Last Revision Dates.
Initials:_____

DAMAGED PRODUCT: Product delivered to jobsite that is received damaged, must be reported to our Trade Project Coordinator Dept within 10 calendar days of date of delivery. Damaged product reported after 10 calendar days of delivery will be considered jobsite damage and will be billable by our company.

MISSING PRODUCT: Product delivered by our company and found to be missing from the jobsite must be reported to our Trade Project Coordinator Dept within 5 calendar days of the delivery date, or the product will be considered stolen or disposed of at the jobsite and replacement product will be billable by our company.

Remodeling or Replacement :

PAYMENT TERMS:

Orders placed by homeowners require a 50% down payment in advance of the order being placed. For remodeling or replacement jobs installed by our company, the customer can withhold a maximum of 5% of the contract price until the job is completed to the customer's satisfaction should any issues arise during completion of the work. Service parts ordered by our company which are not covered by the Pella warranty (see WARRANTY paragraph) must be paid for in full prior to scheduling or commencement of any service work by our company.

WARRANTY: Pella® products are covered by Pella's limited warranties in effect at the time of sale. All applicable product warranties are incorporated into and become a part of this contract. Please see the warranties for complete details. Neither Pella Corporation nor Pella Products of Omaha and Lincoln will be bound by any other warranty. Please be aware that product which is not fully paid for is not covered by the warranty.

RETURN FEES: A 50% Fee will be charged for all items cancelled by the customer after the Last Revision Date. Your salesrep can provide you with information related to Last Revision Dates.
Initials:_____

PREFINISHING: For remodeling or replacement orders placed by homeowners, Pella Products of Omaha and Lincoln offers painting & staining applications prior to installation of our products. The stain color sample is only a general representation of the final product. Variations in different batches of stain along with natural differences in absorption rates, grain color, and characteristics of veneers and solid woods can and do affect the final wood color. Such variations will be considered normal and not cause for replacement. We will not accept returns based upon stains not matching samples, and will not issue monetary credit for any variation in final stain color from the sample.

Stain Color _____
Initials:_____

WINDOW TREATMENTS: Your new windows are custom made for your opening. Pella manufactures it's product to be of the highest quality in order that your new windows will be more energy efficient. Every Manufacturers frame is unique in profile and fit. It is possible that your existing interior mounted blinds or shades will no longer fit inside our frames. It is also possible that your existing shutters may not fit on your new energy efficient windows. Pella will not be responsible for these items and will not issue monetary credit or pay for any replacement blind or shades necessitated by the replacement of your windows.
Initials:_____

SECURITY SYSTEMS: During installation of Buyer's new windows and/or doors, security system wires and/or hardware may be damaged. Buyer is responsible for the coordination of their security system being disconnected prior to installation and reconnected after installation with a third party. Buyer acknowledges that Pella will not be responsible for these items and will not issue monetary credit or pay for any replacement of security hardware necessitated by the replacement of Buyer's windows.
Initials:_____

INSTALLATION IN EIFS/STUCCO: During installation of Buyer's new windows and/or doors in homes with EIFS or Stucco, Pella Windows and Doors will cut back the EIFS or Stucco to install

Buyer's new windows and/or doors. Buyer is responsible for the coordination of EIFS or Stucco work after installation of windows and/or doors through a 3rd party. Buyer is also responsible for coordinating the caulking of windows after completion of EIFS or Stucco work through a 3rd party. Buyer acknowledges that Pella will not be responsible for these items and will not issue monetary credit or pay for any EIFS work, Stucco work, or caulking associated with these types of installs necessitated by the replacement of Buyer's windows.
Initials:_____

RIGHT TO RENOVATE: If your home was built prior to 1978, a lead test must be performed by the contractor prior to Pella performing any installation services.

BUILDING PERMITS: It is the responsibility of the contractor to pull any and all permits necessary prior to Pella performing any installation services.

DAMAGED PRODUCT: Product delivered to jobsite that is received damaged, must be reported to our Trade Project Coordinator Dept within 10 calendar days of date of delivery. Damaged product reported after 10 calendar days of delivery will be considered jobsite damage and will be billable by our company.

MISSING PRODUCT: Product delivered by our company and found to be missing from the jobsite must be reported to our Trade Project Coordinator Dept within 5 calendar days of the delivery date, or the product will be considered stolen or disposed of at the jobsite and replacement product will be billable by our company.

Invoices will be submitted to the customer upon installation with the deposit applied first, with invoices for installations due in 30 days or when the project is substantially complete. Substantial completion is defined at the point when work is nearly complete, and the building can be occupied and used as intended. For remodeling or replacement jobs installed by our company, the customer can withhold to a maximum of 5% of the contract price until the job is completed to the customer's satisfaction should any issues arise during completion of the work. Service parts ordered by our company which are not covered by the Pella warranty (see WARRANTY paragraph) must be paid for in full prior to scheduling or commencement of any service work by our company.

Initials:

Each multi-panel and multi-slide system needs an approved design analysis and Pella Corporation stamped shop drawings signed off on prior to ordering. Since the products do not have an air and water performance rating, both overhangs and water managing patios or sloping are required. All multi-slide systems must have a minimum overhang of 50% of the height of the door for weather protection. All labor, product, and factory warranties will be voided without the minimum overhang requirements. Pella Windows & Doors of Omaha & Lincoln recommends a level rough opening for optimal performance. If the opening isn't level or doesn't include a slope away from the system, warranty exclusions will be applied.

Initials: _____

☐ **Project Checklist has been reviewed**

Customer Name (Please print)

Pella Sales Rep Name (Please print)

Customer Signature

Pella Sales Rep Signature

Date

Date

Credit Card Approval Signature

Order Totals	
Taxable Subtotal	$34,753.75
Sales Tax @ 0%	$0.00
Non-taxable Subtotal	$5,515.90
Total	$40,269.65
Deposit Received	$0.00
Amount Due	**$40,269.65**