



1514 South Saddle Creek Rd
Omaha, NE 68106
402-453-5730

Futuramic's Clean Water Center/Stryker
Rentals
1514 S Saddle Creek Rd, Omaha, Nebraska
68106 United States
(402) 453-5730

Estimate 167549549
Job 167547362
Estimate Date 7/29/2026
Customer PO

Billing Address

MCNEIL COMPANY / CROCKETT RESIDENCE
4666 South 132nd Street
Omaha, NE 68137 USA

Job Address

MCNEIL COMPANY / CROCKETT
RESIDENCE
1702 South 150th Avenue
Omaha, NE 68144 USA

Estimate Details

RO drinking water option 2: Custom RO with Walrus pump: Installation and tax included in price. Install Futuramic's Clean Water Center 5 stage reverse osmosis drinking water system in basement utility room (area of installation to be discussed with builder/plumber/customer, as preferred install location will be closest to primary service areas) with 25 gallon atmospheric tank and Walrus delivery pump and 10" slimline carbon post filter. Plumber to run 1/2" cpvc or pex lines to all locations needing drinking water (per contractor: RO system to feed to LL Bar sink, Kitchen sink, Kitchen fridge/freezer, Pantry sink, Pantry ice maker, Pantry fridge/freezer) and then either connect to a "home run" to RO install location OR a manifold at install location with individually labeled lines to each location for Futuramic to connect to. Plumber to connect supply lines to valves at install locations for refrigerators and ice makers. Futuramic to make all other locations at install.

Service #	Description	Quantity	Your Price	Your Total
IN-WT-FCWC5RO	Installation Details - Run domestic plumbing lines in and out of the unit properly securing pipe to limit movement of piping. - Run discharge tubing from unit to drain (using code approved methods) properly securing tubing to limit movement of piping. - All work will be completed up to local plumbing code.	1.00	\$1,644.50	\$1,644.50
IN-WT-TANK25	Installation Details - Install 25 Gallon Atmospheric Storage Tank with Shut-off - Install Carbon Filter Post Pressurization	1.00	\$451.00	\$451.00
IN-WT-HQ-800H-PUMP	Installation Details Install 1hp RO Product Delivery Pump	1.00	\$1,324.80	\$1,324.80
E-WT-FCWC5RO	FCWC75 RO 5 STAGE 75 GPD REVERSE OSMOSIS SYSTEM - Stage 1- Sediment - Stage 2- Pre-Carbon - Stage 3- Pre-Carbon - Stage 4- 75 GPD Membrane - Stage 5- In-line GAC Aluminum96-98%Floride93-95%Arsenic (+5)94-96%Lead96-98%Bacteria99+%Magnesium94-96%Cadmiu95-97%Mercury95-97%Calcium94-97%Nitrate92-95%Chlorine90-95%Phosphate97-98%Chloride90-95%Silver95-97%Copper96-98%Sodium94-98%Cyanide90-95%Zinc96-98%	1.00	\$0.00	\$0.00
FARRIS FCWC 75 RO				
E-WT-TANK25	ATMOSPHERIC TANK 25 gallon	1.00	\$0.00	\$0.00
Ace Rotomold				
#E-WT-ATMO-TANK-ASSY	Fittings for Atmospheric Tank Assembly 7-Gallon to 50-Gallon	1.00	\$0.00	\$0.00
E-WT-FH2510SLIM-BLU-PR-1/2	SLIMLINE HOUSING 2.5" X 10" BLUE W/ PR 1/2" 158195	1.00	\$0.00	\$0.00

PENTAIR E-WT-HQ-800H- PUMP	WALRUS 1 HP DELIVERY PUMP	1.00	\$0.00	\$0.00
----------------------------------	---------------------------	------	--------	--------

Features

- The HQ is a complete, all-in-one unit, consisting of pump, motor, pressure tank, and electronic controller. The built-in electronic controller ensures that the pump starts automatically when water is consumed and operates continuously until water is not required. It will also protect the pump when it is in faulty conditions.
- Compact design and quiet operation make the HQ series suitable for many applications.
- Impellers are constructed of stainless steel for greater durability.
- The built-in indicator lights on top panel will display the pump's working condition and diagnosis.
- The built-in protective functions will shut off the pump and automatically reset in case of: Dry run, Excessive Temperature, Rapid Cycling
- Newly designed cast aluminum motor for higher efficiency and lower amperage draw

WALRUS HQ-800H

#	Description	Total
DIS-5PERCENT	General 5% discount	-\$171.02
		Sub-Total \$3,249.28
		Total \$3,249.28
		Est. Financing \$53.94

Thank you for choosing Futuramic`s Clean Water Center/Stryker Rentals

THIS IS AN ESTIMATE, NOT A CONTRACT FOR SERVICES. The summary above is furnished by Futuramic`s Clean Water Center/Stryker Rentals as a good faith estimate of work to be performed at the location described above and is based on our evaluation and does not include material price increases or additional labor and materials which may be required should unforeseen problems arise after the work has started. I understand that the final cost of the work may differ from the estimate, perhaps materially. THIS IS NOT A GUARANTEE OF THE FINAL PRICE OF WORK TO BE PERFORMED. I agree and authorize the work as summarized on these estimated terms, and I agree to pay the full amount for all work performed.