

Sent by Bob Sargent on Aug 3, 2026

Sent



13530 L Street
Omaha, NE 68137
Phone: 402-238-3272

McNeil Company
Phone: 402.333.1462

4666 South 132nd Street
Omaha, NE 68137

Job Address:
1702 South 150th Avenue
Omaha, NE 68144

Print Date: 8-3-2026

Proposal for 1702 S 150th Ave - Crockett Res - McNeil

Proposal good for 30 days. Acceptance of this proposal is an agreement with Larry Peterson Construction to frame your project. Scheduling will be done in a timely manner based on the date of acceptance of this proposal and previously accepted work prior to the date of your acceptance.

"This proposal is not a contract and no contract is formed until the general contractor and Larry Peterson Construction agree to and execute a formal contract."

Notes to General Contractors

Fall Protection Installation and Responsibility:

LP Construction will install fall protection at windows, doors, and stair openings as required for safety. Once properly installed, the fall protection may not be removed, altered, or relocated by any other trade.

If fall protection is removed or altered by other trades, LP Construction shall not be held responsible for any safety incidents, compliance violations, or liabilities arising thereafter. Responsibility for reinstallation or replacement of fall protection after removal shall rest solely with the trade(s) who removed it.

We have seen a change in the services provided by some of your lumber suppliers. As a Framing Contractor with multiple people on a project at any given time, having a complete material package is essential. We have seen shortages on almost every single project we have been contracted to frame. We must continually run after items due to shortages. It has gotten out of control, costing LPC money running after materials and employees waiting for materials. Effective October 1, 2020, there will be a charge for every trip we have to make to the lumberyard to pick up materials. We do not want to charge you this fee as you do not want to pay it. Please verify your lumber packages are complete prior to us starting your project.

All wire transfers made to Larry Peterson Construction will only be accepted in the following manner. You must make direct contact with Larry Peterson for approval prior to the transfer, either by phone, text or email, and confirm details, including amount, location for pickup and method of transfer. If this process is not followed, Larry Peterson Construction accepts no responsibility for where the monies have been sent.

Thank you – LPC Management Team

Items	Description	Qty/Unit	Unit Price
3200 - Framing Labor	Bid To: McNeil Builders Bid For: Framing Labor Project: Crockett Residence Address: 1702 South 1150th Avenue, Omaha NE This is a Wood Framing Labor Bid Only! LP Construction Will Provide Pneumatic Fasteners Only! Bid Includes: 2960 Sq. Ft. Main Floor 1666 Sq. Ft. Upper Level 1121 Sq. Ft. Garage 50 Sq. Ft Covered Front Porch 544 Sq. Ft. Covered Back Porch Stick Framing of all Walls 10' & 11' Foundation Walls 50 Ln. Ft. Of Half & Full Walkout Wall Framing 7 Steel Beams to Set in Basement Stairs from Basement to Main Floor with Landing 18" Floor Trusses 23/32" Advantech Sub-floor Glued & Screwed 10' Main Floor Walls 9' Front Study Wall Height 11' 6" Great Room Ceiling Height Master Bedroom Vault Boxed Out Cantilever @ Master Bedroom with Raised Walls & Shed Roof Boxed out Master Tub Raised Wall & Shed Roof Dining Room Cathedral Ceiling with Lowered Sloped Ceiling Great Room Vault Great Room Fireplace Framing with Arches on sides Dropped Ceiling over Master Tub Kitchen Boxed out Window 4 Pocket Doors to Frame on Main Floor Dropped Soffits on Main Floor called out on Print Arched Openings Main Floor Curved Drywall Kitchen Wall Framing per Detail Ceiling Vault in Study Arched Ceiling @ Covered Entry & Foyer Stair Hall Vault Stairs to 2nd Floor with 2 Landings 8' Walls 2nd Floor Bedroom #4 Vault Bedroom # 2 & 3 Clipped & Sloped Ceiling Sitting Room Barrel Ceiling Sitting Boxed out Vault with Curved Roof Complete Roof Truss Package 7/12 & 10/12 Off Pitch Roof 2/12 Back Covered Porch Roof Truss Pitch 14/12 2 Front Gable Roofs Exterior Fireplace Chase to Frame Outdoor Living Room Fireplace Framing 7/16" Zip Wall Sheathing 7/16" Roof Sheathing LP Pre-vented Smart Soffit figured for Overhangs ALT: Basement Framing Includes All Walls Framed throughout Basement per Print Soffits shown on Print Does Not include Step into Golf Sim Room as it is not shown on Print! Add \$9,670.00 to this Quote Note: No Change in Price if Golf Sim Room is Framed or is not Framed, same amount of Walls for each option! Does Not Include: Ceiling Soffit on Underside of Porches Soffits not shown on Print Setting Doors or Windows Setting Pocket Door Frames Exterior Trim or Siding Outdoor Kitchen Framing T & G Soffits	1	\$108,784.00

Does Not Include: Any Building Permits, Felt, Ice & Water Shield or Zip Tape on Roof, Flashings, Siding, Exterior Trim, James Hardi Soffit, Any T&G or OSB on underside of covered porches and soffits, Installation of Aluminum Soffits, Corbels, Wood Brackets, Front Gable Arched Cedar Beams, Finished Exterior Deck & Railing, Deck Stairs or Landings, Return trips for wood post/columns, Decorative Columns, Dropped Ceilings or Soffits shown on Print, Outdoor Kitchen Framing, Installation of Pocket Door Frames (framing only) - Pocket Door Frames must be set by Trim Carpenter, **Installation or Assembling of Doors or Windows, Setting of Sliding or Hinged Patio Doors. If we are requested to set doors and windows, Dupont 8" Flex Tape (for sill plate), window tape for the nailing flange and Shims will be required to be on site. Multi Operating Patio Doors will not be set.**

General Contractor or Builder shall Supply: All Materials and Building Permits.

Conventional framing of floor system or incomplete roof truss system not shown on print at time of proposal will add additional charges to the project.

If we are unable to get a lift around the structure, additional charges will apply for building scaffolding.

Not responsible for existing Landscaping or Concrete.

220 Power Supply must be provided when starting the Job.
LP Construction will supply all Pneumatic Fasteners.

Bob Sargent
Client Service Manager
bob@lpcomaha.com
402.980.9221

I confirm that my action here represents my electronic signature and is binding.

Signature:

Date:

Print Name: