

PROPOSAL

8-5-26

RON MULLER CONSTRUCTION CO.

4630 South 150th Street

Omaha, Nebraska 68137

(402) 301-9633

Mc Neil Company

Crockett Residence

1702 S. 150th Ave

Page # 1

Bid # 1

Labor only bid for stone veneer on outside of the home. For full depth stone labor is for flashing, weeps, tarpaper, for thin stone installing tarpaper, rain screen, wire lath, mortar scratch coat, and installation of stone and stone sills. Labor also includes laying precast around windows and underneath doors.

Thin stone 1,000 sq. ft x \$14.⁰⁰ sq. ft = \$14,000.⁰⁰

1,000 sq. ft of rain screen & scratch coat x \$3.⁰⁰ sq. ft = \$3,000.⁰⁰

Full depth stone 1,260 sq. ft x \$25.⁰⁰ sq. ft = \$31,500.⁰⁰

280 feet of stone sills x \$8.⁰⁰ a foot = \$2,240.⁰⁰

Thin stone chimney 200 sq. ft x \$20.⁰⁰ sq. ft = \$4,000.⁰⁰

200 sq. ft of rain screen & scratch coat x \$3.⁰⁰ sq. ft = \$600.⁰⁰

pour a concrete cap = \$1,100.⁰⁰

scaffold building = \$900.⁰⁰

Lay precast around windows = \$4,500.⁰⁰

Lay precast underneath doors = \$600.⁰⁰

Install flashing & weeps = \$700.⁰⁰

Sample boards = \$600.⁰⁰

** Bid does not include labor for

installing stone slabs on outdoor grill

& fireplace

\$63,740.⁰⁰

PROPOSAL

RON MULLER CONSTRUCTION CO.

4630 South 150th Street
Omaha, Nebraska 68137
(402) 301-9633

8-5-26

Page # 2

Bid # 2

Mc Neil Company
Crockett Residence
1702 S. 150th Ave

Great Room Fireplace

Labor only to install stone and precast surround
around fireplace. Total labor is \$1,800.00

Bid # 3

Master bath stone

150 sq. ft of stone x \$20.00 sq. ft = \$3,000.00

Thank You,
Jahid Samir