

ESTIMATE

Musicfield Concrete

18911 Sahler St
Elkhorn, NE 68022

mt@musicfieldconcrete.com
+1 (402) 699-2856
www.musicfieldconcrete.com



musicfieldconcrete
construction

Bill to

McNeil Company Builders
4666 S 132 St
Omaha, NE 68137

Estimate details

Estimate no.: 2141
Estimate date: 08/05/2026
Expiration date: 09/05/2026

Description	Amount
ALL WORK IS LOCATED AT CROCKETT RESIDENCE	\$23,240.25
Install basement floor	
-approx. 2,817 sq'	
-4" thick concrete	
-crushed concrete subgrade	
-compact all areas	
-steel trowel finish	
concrete mix: L10-4000 no AE	
Install garage floor	\$9,808.75
-approx. 1,121 sq'	
-5" thick	
-crushed concrete subgrade	
-steel trowel finish	
-concrete mix: L10-4000 no AE	
Install driveway	\$12,900.00
-approx. 1,500 sq'	
-5" thick concrete	
-crushed concrete subgrade	
-compact all areas	
-light broom finish	
-joints cut w/ early entry saw	
-approach to be 7" thick per City Of Omaha standard plate	
-concrete mix: L10-4000 AE	
Install service walk to house	\$2,180.60
-approx 260 sq'	
-4" thick concrete	
-crushed concrete subgrade	
-compact all areas	
-light broom finish	
-install (1) 6x12"x7.5" step to stoop	
-concrete mix: L10-4000 AE	

Install stoop to front door of house -approx 50 sq'	\$600.00
Install covered patio -approx 620 sq' -4" thick concrete -crushed concret subgrade -compact all areas -light broom finish -joints cut w/ early entry saw -concrete mix: L10-4000 AE	\$5,332.00
Install steps to pool deck - (7) 4'x12"x7.5" -light broom finish	\$1,050.00
Install pool deck -approx. 906 sq' -4" thick concrete -crushed concrete subgrade -compact all areas -light broom finish -joints cut w/ early entry saw -concrete mix: L10-4000 AE	\$7,791.60
Install trench drain in pool deck -approx. 75 LF -Zurn 880 drain system -install approx 100 LF of pipe daylight out of wall for drain Pricing for drain subject o change based upon location of outlet for drains	\$10,929.00
Install lower patio -approx 620 sq' -4" thick concrete -thickened slab to 6" for hot tub -crushed concrete subgrade -compact all areas -light broom finish -concrete mix: L10-4000 AE	\$5,580.00
Install steps from pool deck to lower patio - approx. (12) 5'x12"x7.5" -light broom finish	\$3,600.00
all work excludes: cold weasther concrete vapor barrier reinforced concrete slabs seal/caulking concrete pumping (Note: concrete puming will likely be needed on this project) rough/finish grading inspections testing any other work not listed in scope hand cut joints	
Note: Pricing subject to change based upon cost of materials and labor	

Note to customer

If existing concrete/asphalt is found to be thicker than estimated and/or contain steel reinforcement additional costs may be added to cover the extra expense of tear out.
If mud needs to be removed from the sub grade extra cost may be applied to cover the added expense of site prep.
Musicfield Concrete is not responsible for damage that may occur to sprinkler systems. But can make small repairs to damaged systems for a fee.
Never use deicers on any concrete surface. Deicers may disintegrate the concrete causing surface scaling

Expiry date09/05/2026

Accepted dateAccepted by