

PROPOSAL

RON MULLER CONSTRUCTION CO.

4630 South 150th Street

Omaha, Nebraska 68137

(402) 301-9633

McNeil Company

13651 Cumins St.

Schachne Residence

1-10-25

Labor only bid for stone veneer on outside of the house and window wells and planters. The bid is for installing rain screen, drip strip, wire lath, mortar scratch coat, stone and stone sills.

Labor

1,800 sq ft of stone x \$14.⁰⁰ sq.ft = \$25,200.⁰⁰

1,800 sq ft of scratch coat x \$2.⁰⁰ sq.ft = \$3,600.⁰⁰

260 feet of stone sills x \$4.⁰⁰ a foot = \$1,040.⁰⁰

Lay precast underneath front door and patio = \$350.⁰⁰

Lay caps on planter and window wells = \$900.⁰⁰

Total labor = \$31,090.⁰⁰

material

Structure bond material to plaster on inside window wells. 6 bags x \$30.⁰⁰ a bag = \$180.⁰⁰

Thank You,

Todd Muller