

Baltazar's Stone, Inc.

10890 Sapp Brothers Dr. Omaha, NE 68138
402 614-8006

Estimate

Date Estimate #
9/29/26 27337

Customer Name

McNeil Residence Builders
4666 S. 132nd St.
Omaha, NE 68137

Ship To

Crockett Residence
1702 S 150th Ave
Omaha, NE 68144

P.O. No.	Terms	Rep	Installer	Project		
	Net 30	GS		FINAL SELECTION MANITOWAC TUMBLED		
Description				Qty	Rate	Total
NATURAL FULLBED STONE INSTALLATION					0.00	0.00
Natural Stone Veneer - Full Bed MANITOWAC DIMENSIONAL (NO RUST)				7.5	650.00	4,875.00T
P1 - LIMESTONE SILL 4" - 3" @ 2" x 6" x LF				80	20.00	1,600.00T
P3 - LIMESTONE TRIM 6" x 4" x 100"				1	291.66	291.66T
Setting Materials for Fullbed; Felt paper jumbo Tex, wall ties, wall straps, drip edge, membrane flashing, termination bar, Xseal 3" tape, masonry seal caulk, nails, screws, anchors, mortar net, weep Vents Quad, and acid wash.				300	3.75	1,125.00T
Mortar - Ash Grove Type S 3000 LB D- White				1	405.00	405.00T
Pallets Wood				1	28.00	28.00T
In-town Delivery By Baltazar's				1	255.00	255.00T
Labor - Fullbed Stone & Sills Installation				300	20.00	6,000.00
Labor - P3 Specialty Trim Installation				1	350.00	350.00
PLINTH INSTALLS					0.00	0.00
(IF THESE STONES ARE BEING INSTALLED IN PLACE OF THIN VENEER THEN SUBTRACT 260 SQUARE FEET OF VENEER STONE & INSTALL)						
Setting Materials for Stone; Wall Ties, Tap Cons, Screws, Anchors as Needed				1	395.00	395.00T
P6 - LIMESTONE PLINTH 24" x 4" x LF (PRICE IS PER LINEAR FOOT) (ONLY FIGURED THE VISIBLE ONES ON PLANS)				140	110.00	15,400.00T
P7 - LIMESTONE TRIM 12" x 2 3/4" x LF (PRICE IS PER LINEAR FOOT) (NONE FOUND ON PLANS)				1	70.00	70.00T
Labor - Exterior Stone Installation Per Linear Foot				130	32.00	4,160.00
EXTERIOR THIN VENEER STONE INSTALLATION					0.00	0.00
Natural Stone Veneer - Unique Custom Blends - Cottage Tumbled - Flats MANITOWAC (NO RUST)				1,500	11.49	17,235.00T
Natural Stone Veneer - Unique Custom Blends - Cottage Tumbled - Corners MANITOWAC (NO RUST)				245	15.50	3,797.50T
P2 - LIMESTONE TRIM 2 1/2" x 6" x LF				90	22.50	2,025.00T
P4 - LIMESTONE TRIM 2 1/2" x 8" x LF				110	33.33	3,666.30T
P5 - LIMESTONE TRIM 2 1/2" x 10" x LF				22	58.33	1,283.26T
Felt Paper Jumbo Tex 240 - 240 sq.ft. Roll				8	26.00	208.00T
KEENE-DR Rain Screen 020, 0.25 thick 48in wide, 65ft long 260 sq ft per roll, Self Draining System. 6 Mill.				7	165.00	1,155.00T
WIRE Lathe 2.5 Galv. Self Furring 17 sq ft per item				110	17.95	1,974.50T
Mortar - Ash Grove - Grey Type S 80 LB				80	9.95	796.00T
Mortar - Ash Grove - White Type S 80 LB				80	19.95	1,596.00T
Pallets Wood				4	28.00	112.00T
In-town Delivery By Baltazar's				4	255.00	1,020.00T
Labor - Exterior Stone Installation				1,550	11.00	17,050.00
Labor - P2, P4, P5 Exterior Stone Trim/Banding Installation				222	18.00	3,996.00
EXTERIOR CHIMNEY EIFS INSTALLATION					0.00	0.00

In an effort to better assist you, we ask you to check the product before installing it to make sure it is the correct color and style.
There are no returns after the stone product as been installed.

Baltazar's Stone, Inc.

10890 Sapp Brothers Dr. Omaha, NE 68138
402 614-8006

Estimate

Date Estimate #
9/29/26 27337

Customer Name

McNeil Residence Builders
4666 S. 132nd St.
Omaha, NE 68137

Ship To

Crockett Residence
1702 S 150th Ave
Omaha, NE 68144

P.O. No.	Terms	Rep	Installer	Project		
	Net 30	GS		FINAL SELECTION MANITOWAC TUMBLED		
Description				Qty	Rate	Total
EIFS Body Walls Materials: Gold Coat-/Back Stop Flash, 1.5" Thick, x 24" x 48" foam, wind locks, base coat, field mesh, detail mesh and Acrylic color tinted finish.				165	6.75	1,113.75T
EIFS - 1" x 8" Band. Includes foam, fiber mesh, thin set-base coat and finish				20	6.00	120.00T
EIFS - 1" x 3" Band. Includes foam, fiber mesh, thin set-base coat and finish				20	5.00	100.00T
Equipment Rental/Fuel -- Per Equipment Rental rate Plus Delivery & Pick up.				1	2,650.00	2,650.00T
In-town Delivery By Baltazar's				1	255.00	255.00T
Labor - EIFS Installation on ROOF				150	19.00	2,850.00T
Labor - EIFS TRIM				1	750.00	750.00
EIFS INSTALLATION					0.00	0.00
EIFS Body Walls Materials: Gold Coat-/Back Stop Flash, 1.5" Thick, x 24" x 48" foam, wind locks, base coat, field mesh, detail mesh and Acrylic color tinted finish.				1,925	6.95	13,378.75T
ES - 1 EIFS Banding 1" x 4" Band, Includes foam, fiber mesh, thin set-base coat and finish				250	4.00	1,000.00T
ES - 2 EIFS Banding 1" x 6" Band, Includes foam, fiber mesh, thin set-base coat and finish				145	4.50	652.50T
ES - 3 EIFS Banding 2" x 4" Band, Includes foam, fiber mesh, thin set-base coat and finish				50	6.00	300.00T
ES - 4 EIFS Banding 2 1/2" x 6" Band, Includes foam, fiber mesh, thin set-base coat and finish				55	8.00	440.00T
ES - 5 EIFS Banding 2 1/2" x 10" Band, Includes foam, fiber mesh, thin set-base coat and finish				35	12.00	420.00T
In-town Delivery By Baltazar's				2	255.00	510.00T
Labor - EIFS Body				1,825	9.95	18,158.75T
Labor - EIFS Banding				535	13.00	6,955.00
In an effort to better assist you, we ask you to check the product before installing it to make sure it is the correct color and style. There are no returns after the stone product as been installed.				Subtotal		\$140,522.97
				Sales Tax (5.5%)		\$5,569.41
				Total		\$146,092.38